

McGuire Air Force Base Restoration Program Site # SS-24

Interim Remedial Action




U.S. AIR FORCE

John G. Pohl, Restoration Program Manager


NJDEP Triad Approach Meeting September 4th, 2003




- History of McGuire Restoration Site # SS-24
- **FASTRAC**
- SS-24 Interim Remedial Action
- **Summary**




2























ISSUES

FEB 03 - Geoprobe Sample taken at the former Building 2227 site, revealed high levels of organic contaminants & breakdown products in groundwater in this area.

☐ Tetrachloroethene (PERC) at a maximum concentration of 13,754 μg/L Regulatory Level 1μg/L

10







FAST TRACK PLAN

- □ 01 APR 03 Expeditiously characterize this site and develop a remedy
- ☐ Proceed with constructing the hangar on the site.

3



SS-24 Interim Assessment and Remedial Action

- Tasks
 - □ Secure/Realign Funding
 - □ Develop SOW
 - □ Award Contract
 - **□** Develop Work Plan
 - ☐ Secure Regulator Approval of Work Plan
 - **□** Complete Characterization
 - ☐ Develop Interim Removal Action Plan
 - ☐ Secure Regulator Approval of IRA Plan
 - □ Execute IRA

14








 Incorporates key elements from other expedited assessment methods










- High level of key stakeholder interaction
- Requires experienced

 FIGURE Technical Team
 (FTT) empowered to
 make decisions in the field
 Completes projects faster,
 cheaper, and with greater
 regulatory satisfaction









Soil and groundwater sampling tools:

- CPT discrete soil and GW samplers
- Percussion direct push discrete soil and GW samplers
- MIP subsurface VOC sampler

Soil and GW analytical tools

- FID/PID/ECD for MIP VOCs
- DSITMS for VOCs in discrete soil and GW
- Off site lab for VOCs in selected discrete soil and GW



September 2003 5



McGuire AFB, NJ C17 Hanger Site Investigation

U.S. AIR FORCE

The problem:

Construction of a new hanger for C17 aircraft delayed by recently discovered potential CI solvent source.


Very limited GW sampling indicated up to 1% of solubility limit PCE


Same data indicated limited distribution of shallow dissolved phase


Apparent dechlorination underway at site


Construction to resume in June 03
























September 2003 7










September 2003 8





STATUS

- Tasks (As of 2 AUG 03)
 - ✓ Secure/Realign Funding
 - ✓ Develop SOW
 - ✓ Award Contract
 - ✓ Develop Work Plan
 - ✓ Secure Regulator Approval of Work Plan
 - **✓** Complete Characterization
 - ✓ Develop Interim Removal Action Plan
 - ✓ Secure Regulator Approval of IRA Plan
 - **□** Execute IRA

34





Keys to project success:

- **FASTRAC** Total Restoration Approach
- Outstanding teamwork
- **■** Excellent communications
- Synergistic teaming between the AF, regulators and the FTT
 - **■** Common goal
 - Trust
 - Motivated "A-Team" across the board
- Top cover from command

36